

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-147-20739-00-00
Spot: SWSESENE Sec/Twnshp/Rge: 14-1S-19W
2854 feet from S Section Line, 449 feet from E Section Line
Lease Name: DAWNDY Well #: 1
County: PHILLIPS Total Vertical Depth: 3540 feet

Operator License No.: 31569
Op Name: BACH, JASON DBA BACH OIL PRODUC
Address: PO BOX 723
ALMA, NE 68920

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3541		600 SX
SURF	8.625	220		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/03/2016 8:30 AM
Plug Co. License No.: 31569 Plug Co. Name: BACH, JASON DBA BACH OIL PRODUCTION
Proposal Rcvd. from: DALE FERLAND Company: BACH, JASON DBA BACH OIL PRO Phone: (785) 302-1435

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement, 11 sx gel and 300 # hulls.
Production perforations: 3341' - 3485'.

Plugging Proposal Received By: PAT BEDORE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/03/2016 11:00 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Hooked to 5 1/2" casing and pumped 75 sx cement w/300 # hulls followed by 11 sx gel.
Pumped 165 sx cement. Max pressure 1700 psi. Hooked to 8 5/8"x 5 1/2" annulus and
pressured to 400 psi immediately.
GPS: 39.96639N -099.42372W

Perfs:

Top	Bot	Thru	Comments
3475	3485		
3456	3466		
3341	3344		

Remarks: GLOBAL CEMENTING TICKET # 2549

Plugged through: CSG

District: 04

Signed _____

Pat Bedore

(TECHNICIAN)

CM

KCC WICHITA

MAR 11 2016

RECEIVED

720
3-17-16
Form CP-2/3

MAR 07 2016