

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-147-20731-00-00
Spot: SESENESE Sec/Twnshp/Rge: 10-2S-19W
1400 feet from S Section Line, 200 feet from E Section Line
Lease Name: LEOTA Well #: 1
County: PHILLIPS Total Vertical Depth: 3630 feet

Operator License No.: 31569
Op Name: BACH, JASON DBA BACH OIL PRODUC
Address: PO BOX 723
ALMA, NE 68920

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD | 5.5 | 3630 | | 600 SX |
| SURF | 8.625 | 218 | | 175 SX |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/07/2016 9:30 AM
Plug Co. License No.: 31569 Plug Co. Name: BACH, JASON DBA BACH OIL PRODUCTION
Proposal Rcvd. from: DALE FERLAND Company: BACH, JASON DBA BACH OIL PRO Phone: (785) 302-1435

Proposed
Plugging
Method:

Ordered 300 sx 60/40 pozmix 4% gel cement, 11 sx gel and 300 # hulls.

Plugging Proposal Received By: PAT BEDORE WitnessType: NONE
Date/Time Plugging Completed: 03/07/2016 1:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Hooked to 5 1/2" casing and pumped 75 sx cement w/300 # hulls followed by 11 sx gel.
Pumped 180 sx cement with a maximum pressure of 1500 psi. Hooked to 8 5/8" x 5 1/2"
annulus and pressured to 300 psi immediately.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3562 | 3573 | | |
| 3465 | 3469 | | |
| 3448 | 3455 | | |

Remarks: GLOBAL CEMENTING

Plugged through: CSG

District: 04

Signed _____

Pat Bedore

(TECHNICIAN)

CM

KCC WICHITA

MAR 11 2016

RECEIVED

no
3-17-16

Form CP-2/3

MAR 3 7 2016