

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-06890-00-01
Spot: NWNESWSW Sec/Twnshp/Rge: 17-14S-14W
1313 feet from S Section Line, 4384 feet from E Section Line
Lease Name: VAUGHN Well #: 6
County: RUSSELL Total Vertical Depth: 3309 feet

Operator License No.: 34318
Op Name: BEREXCO LLC
Address: 2020 N. BRAMBLEWOOD
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.05	3301		100 SX
SURF	8.065	351		115 SX

Well Type: OIL UIC Docket No: E21434.1 Date/Time to Plug: 02/10/2016 9:30 AM
Plug Co. License No.: 34318 Plug Co. Name: BEREXCO LLC
Proposal Rcvd. from: JEREMY HANKINS Company: BEREXCO LLC Phone: (316) 265-3311

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls.
5 1/2" casing. DV Tool at 840' w/240 sx cement circulated.
Ran 4 1/2" liner w/100 sx cement in on recompletion. Squeezed at 354' and 900'.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/11/2016 4:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 3000' and pumped 75 sx cement w/100 # hulls. Pulled tubing to 1880' and pumped 75 sx cement. Pulled tubing to 800' and pumped 105 sx cement with good cement returns. POOH. Hooked to casing and pumped 10 sx cement. Casing below collar leaked. Dug braden head out and found to be full of cement.
11/12/2016- Checked on well and still had iron on casing.
GPS: 38.83094 -098.90695

Perfs:

Top	Bot	Thru	Comments
2899	3122		

Remarks: GLOBAL CEMENTING TICKET # 2540

Plugged through: TBG

District: 04

Signed Ray Dinkel
(TECHNICIAN) CM

KCC WICHITA

MAR 04 2016

RECEIVED

FEB 16 2016

Form CP-2/3

no
3-17-16