

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-135-29518-00-00  
Spot: NWNE Sec/Twnshp/Rge: 36-19S-22W  
4617 feet from S Section Line, 1996 feet from E Section Line  
Lease Name: HL WILLIAMS, EST Well #: 1  
County: NESS Total Vertical Depth: 4378 feet

Operator License No.: 34318  
Op Name: BEREXCO LLC  
Address: 2020 N. BRAMBLEWOOD  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4363	0	WITH 75 SX CMT
SURF	8.625	359		WITH 325 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/03/2016 9:00 AM  
Plug Co. License No.: 34318 Plug Co. Name: BEREXCO LLC  
Proposal Rcvd. from: MARK LEIKER Company: BEREXCO LLC Phone: (316) 265-3311

Proposed Plugging Method: BOTTOM PLUG AT 4300' WITH 35 SX CMT & 150# HULLS. PLUG AT 1506' WITH 40 SX CMT. PERFORATE @ 700' WITH 80 SX CMT OVER CASING VOLME. IF DOESN'T CIRCULATE 150 SX CMT DOWN BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/03/2016 3:45 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 4306' & SPOT 35 SX CMT & 150# HULLS. PULL TBG TO 1522' & PUMPED 40 SX CMT & 150# HULLS. PULL TBG & PERFORATE AT 680'. RUN TBG TO 704' & PUMPED 100 SX CMT. CMT CIRCULATED TO SURFACE. PULLED TBG & TIED ONTO CASING WITH A SWEDGE & PUMPED 80 SX CMT. MAXIMUM PRESSURE WAS 300#. SHUT IN PRESSURE 150#. TIED ONTO BACKSIDE & PUMPED 25 SX CMT. PRESSURED TO 300# & HELD. PULLED SWEDGE & TOPEED OFF WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4363	4375		

Remarks: USED 60/40 POZMIX 4% GEL BY GLOBAL CEMENTING.

Plugged through: TBG

District: 01

Signed Michael Maier  
(TECHNICIAN)

RECEIVED  
MAR - 8 2016  
KCC DODGE CITY

KCC WICHITA  
MAR 11 2016  
RECEIVED

Form CP-2/3  
No 3-17-16