

1 080031

API NUMBER 15- 185-22,611-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

W/2 SW, SEC. 35, T 24 S, R 14 W/E

1320 feet from S section line

4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7261

Lease Name Chappell Well # 1

Operator: Pate-Dombaugh, Inc.

County Stafford 138.94

Name & Address 150 N. MAIN, Suite 804

Well Total Depth 4275 feet

804 Union Center Building

Conductor Pipe: Size _____ feet

Wichita, KS 67202

Surface Casing: Size 8 5/8 feet 258

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie Drilling, Inc. License Number 5442

Address 801 Union Center, Wichita, KS 67202

Company to plug at: Hour: 1 a.m. Day: 18 Month: 10 Year: 1989

Plugging proposal received from Bill Craig

(company name) Abercrombie Drilling, Inc. (phone) 316-262-1841

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 859'

1st plug at Arbuckle with 50 sx cement, 2nd plug at 860' with 50 sx cement,

3rd plug at 290' with 40 sx cement, 4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Mike Spain
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 7:30 a.m. Day: 18 Month: 10 Year: 1989

ACTUAL PLUGGING REPORT 1st plug at 860' with 50 sx cement,

2nd plug at 290' with 40 sx cement,

3rd plug at 40-0' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

Water well plugged with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(if additional description is necessary, use BACK of this form.)

INVOICED
(if not) observe this plugging.

DATE 10-25-89

Signed Steve Chumot
(TECHNICIAN)

INV. NO. 26233

DEC 15 1989

RECEIVED
STATE CORPORATION COMMISSION
OCT 23 1989
CONSERVATION DIVISION
Wichita, Kansas

10-23-89