

1 110055

6-3-87

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-185-21,940-6000

NW NE NW, SEC. 32, T 24 S, R 14 W ~~XX~~
4950 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5087

Lease Name Waters A Well # 1

Operator: Texas Energies, Inc.
Name & Address P.O. Box 947
Pratt, KS 67124

County Stafford 143.33

Well Total Depth 4410 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 307

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 10:30 a.m. Day: 3 Month: 6 Year: 1987

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2474

were: 4 1/2" at 4386' PBDT 4310' Perfs at 4122-28'

1st plug sand back to 4060' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3'sx hulls, 10 sx gel, 50 sx cement, 15 sx gel, and 125 sx cement.

Plugging Proposal Received by Paul Luthi and Dick Kapp
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 11:20 a.m. Day: 3 Month: 6 Year: 1987

ACTUAL PLUGGING REPORT 1st plug sanded back to 4060' and dumped 4 sx cement on top of sand through bailer.

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 15 sx gel, and 125 sx cement.

6-9-87

JUN 9 1987

Maximum pressure 500 psi and shut in 200 psi.

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2730' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

~~INVOICED~~ (did not) observe this plugging.

Signed James Kapp
(TECHNICIAN)

DATE 6-9-87
INV. NO. 17206