

1080243

15-185-00315-0001

Docket No. D-15,312

API NUMBER 15- Completed 2-10-56

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

SW SW SW , SEC. 16 , T 24 S, R 14 W/X  
660 N SE Corner of  
feet from ~~XXX~~ section line  
4620 W SE Corner of  
feet from ~~XXX~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5427

Lease Name Smith Well # 1

Operator: D. R. Lauck Oil Co., Inc.

County Stafford

Name & Address 221 South Broadway, Suite 400

Well Total Depth 4378 <sup>42.2'</sup> feet

Wichita, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 200

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well  D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: noon Day: 24 Month: October Year: 19 84

Plugging proposal received from Melvin Urban

(company name) D. R. Lauck (phone) 316-564-2013

were: 5 1/2" set at 4294' Open Hole

1st plug pump 40 sx cement to 871' Wait for cement to set up

2nd plug tag cement at 670' - pump 140 sx cement and pull tubing

3rd plug pump 20 sx cement to circulate

4th plug pump 100 sx cement into backside

Plugging Proposal Received by J. H. Metz (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 2:30 pm Day: 24 Month: October Year: 19 84

ACTUAL PLUGGING REPORT 5 1/2" set at 4294' Open Hole

1st plug pumped 40 sx cement to 871' and waited 1:45 mins., 2nd plug tagged cement at

670' - pumped 140 sx cement and pulled tubing to 200', 3rd plug pumped 20 sx cement and

circulated, 4th plug pumped 100 sx cement into back side.

Used 500# hulls. Maximum pressure on back side 300 psi and shut in 100 psi

RECEIVED STATE CORPORATION COMMISSION

8-31-84 OCT 31 1984

Remarks: Cemented by Allied.

CONSERVATION DIVISION Wichita, Kansas

(If additional description is necessary, use BACK of this form.)

INVOICED (did not observe this plugging.)

Signed J. A. Metz SWD (TECHNICIAN)

DATE 11-7-84

INV. NO. 4678