

To: 1 041198
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- Docket #D-23,051

NE NE SW, SEC. 16, T 24 S, R 14 W/E
2310 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5427

Lease Name Smith Well # 4
County Stafford 145.60

Operator: D.R. Lauck Oil Co., Inc.
Name:
Address 221 S. Broadway, Ste. 400
Wichita, KS 67202

Well Total Depth 4480 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 227

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ X D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Mike's Testing & Salvage, Inc. License Number 31529
Address P.O. Box 209, Chase, KS 67524

Company to plug at: Hour: 3:45 p.m. Day: 2 Month: 8 Year: 1996

Plugging proposal received from Manny Boatwright 8-7-96
(company name) Mike's Testing & Salvage, Inc. (phone) 316-938-2943

Work: 5 1/2" at 4293' w/100 sx cement, 4 1/2" liner at 4285-4390' w/50 sx cement, Open hole 4390-4480'
1st plug sand back to 4220' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release
8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:30 p.m. Day: 2 Month: 8 Year: 1996

ACTUAL PLUGGING REPORT 1st plug sanded back to 4220' and dumped 5 sx cement on top of sand bridge through bailer,
2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.
Maximum pressure 300 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1400' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE AUG 16 1996
INV. NO. 46269

Signed Stephen J. Pfeifer (TECHNICIAN)