

To: 1 010057
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-21,142 -0000

NE SE NW, SEC. 16, T 24 S, R 14 (W/E)
3630 feet from (S) section line
2970 feet from (E) section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6050

Lease Name Torleumke Well # 1

Operator: Kelso Casing Pulling

County Stafford

Name & Address bought from Quadel Energy Corp.

Well Total Depth 4371 142.06 feet

P. O. Box 347,

Conductor Pipe: Size _____ feet

Chase, KS 67524

Surface Casing: Size 8 5/8 feet 345

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 3:45 pm Day: 16 Month: December Year: 19 85

Plugging proposal received from Millard Kelso

(company name) Kelso (phone) 316-938-2457

were: 5 1/2" at 4349' PBD 4220' Perfs at 4313-15'; 4147-53'; 4103-06'

1st plug sand back to 4050' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 130 sx cement

Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:15 pm Day: 16 Month: December Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 4050' and dumped 5 sx cement, on top of sand through bailer, 2nd plug squeezed well with 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 130 sx cement.

Maximum pressure 300 psi and shut in 50 psi

Remarks: Recovered 2044' 5 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.
(if additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

STATE CORPORATION COMMISSION Signed

Paul A. Luthi
(TECHNICIAN)

DATE DEC 20 1985

12-20-85 DEC 20 1985

INV. NO. 11679

CONSERVATION DIVISION

FORM CP-2/3
Rev. 01-84