

15-185-11008-0000

To: 1 041194
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- Spud date 1/7/56
NE SW SW, SEC. 16, T 24 S, R 14 W/E
990 feet from S section line
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5427
Operator: D.R. Lauck Oil Co., Inc.
Name
Address 221 S. Broadway, Ste. 400
Wichita, KS 67202

Lease Name Smith Well # 2
County Stafford 139.06
Well Total Depth 4279 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 246

Abandoned Oil Well Gas Well Input Well SWD Well D&A
Other well as hereinafter indicated

Plugging Contractor Mike's Testing & Salvage, Inc. License Number 31529
Address P.O. Box 209, Chase, KS 67524

Company to plug at: Hour: 10:30 a.m. Day: 2 Month: 8 Year: 19 96
Plugging proposal received from Manny Boatwright

(company name) Mike's Testing & Salvage, Inc. (phone) 316-938-2943

Work: 5 1/2" at 4277' w/125 sx cement, PBSD 3870', Perfs at 3832-36, 3799-3805', Open hole 4277-79'
1st plug sand back to 3745' and dump 5 sx cement on top of sand bridge through bailer,
2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release
8 5/8" wiper plug and pump 125 sx cement.

8-7-96

RECEIVED
PLUGGING SECTION
AUG 16 1996

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None
Operations Completed: Hour: 11 a.m. Day: 2 Month: 8 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug sanded back to 3745' and dumped 5 sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 800 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 700' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
AUG 16 1996
DATE
INV. NO. 46267

Signed Stephen J. Pfeiffer (TECHNICIAN)