

6-29

To: 1 120270
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-22,593 -0000
NE SW NW, SEC. 15, T 24 S, R 14 W/K
3630 feet from S section line
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5097
Operator: Martin Oil Producers, Inc.
Name & Address: 1010 Union Center
Wichita, KS 67202

Lease Name Wilson Well # 1
County Stafford 134.06
Well Total Depth 4125 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 286

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Allen Drilling Company License Number 5148

Address P.O. Box 1389, Great Bend, KS 67530

Company to plug at: Hour: 12 p.m. Day: 29 Month: 6 Year: 19 89

Plugging proposal received from Craig Christopher

(company name) Allen Drilling Company (phone) 316-793-3582

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 1962' Anhydrite 894-912'

- 1st plug at 912' with 50 sx cement,
- 2nd plug at 310' with 40 sx cement,
- 3rd plug at 40' with 10 sx cement,
- 4th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Stephen J. Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 1:30 p.m. Day: 29 Month: 6 Year: 1989

- ACTUAL PLUGGING REPORT
- 1st plug at 912' with 50 sx cement,
 - 2nd plug at 310' with 40 sx cement,
 - 3rd plug at 40' with 10 sx cement,
 - 4th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
JUL 5 1989 7-5-89
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by HOWCO.
(If additional description is necessary, use BACK of this form.)

INVOLVED observe this plugging.

DATE 7-6-89

Signed [Signature] (TECHNICIAN)

INV. NO. 25217
6-29