

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-20620-00-00
Spot: NWSESE Sec/Twnshp/Rge: 14-24S-15W
1010 feet from S Section Line, 780 feet from E Section Line
Lease/Unit Name: SUITER-ENGLISH REID Well Number: 1-14
County: STAFFORD Total Vertical Depth: 4380 feet

Operator License No.: 5474
Op Name: NORTHERN LIGHTS OIL COMPANY, L
Address: PO BOX 164
ANDOVER, KS 67002

Production Casing Size: 4.5 feet: 4372 WITH 200 SX CMT
Surface Casing Size: 8.625 feet: 527 WITH 325 SX CMT
\$142.35

Well Type: GAS UIC Docket No: E19845.1 Date/Time to Plug: 01/31/2003 1:30 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: SANDED TO 4060' & 4 SX CMT. PLUG AT 1000' WITH 10 SX GEL - 50 SX CMT. PLUG AT 550' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 01/31/2003 2:30 PM KCC Agent: STEVE PFEIFER


Actual Plugging Report:

PBTD 4380'. PERFS AT 4303-08'. SANDED BACK TO 4060' & PUT 4 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. SPOT PLUGS THROUGH 4 1/2" CASING. 1ST PLUG AT 1000' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 550' WITH 50 SX CMT WITH 100# HULLS MIXED IN CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 1810' OF 4 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Stephen J. Pfeifer
(TECHNICIAN)

RECEIVED
FEB 13 2003
2-13-03
KCC WICHITA

INVOICED
DATE 2-14-03
VV. NO. 2003061205