

To: 120753 11-17
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
250 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-22,882-0000 176R
NE NW NW, SEC. 14, T. 24 S, R. 15 W/R

TECHNICIAN'S PLUGGING REPORT

Operator License # 5010
Operator: Knighton Oil Company, Inc.
Name & Address: 221 S. Broadway, Ste. 710
Wichita, KS 67202

Lease Name Doran Well # 1
County Stafford 134.32
Well Total Depth 4133 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 321

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor Duke Drilling Company License Number 5929
Address 310 W. Central, Wichita, KS 67202

Company to plug at: Hour: 9 a.m. Day: 17 Month: 11 Year: 19 92

Plugging proposal received from Lyle Jurgenson
(company name) Duke Drilling Company (phone) 316-267-1331

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 957-975'
1st plug at 960' with 50 sx cement,
2nd plug at 360' with 50 sx cement,
3rd plug at 40' with 10 sx cement,
4th plug to circulate rathole with 15 sx cement, 5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 10:30 a.m. Day: 17 Month: 11 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug at 960' with 50 sx cement,
2nd plug at 360' with 50 sx cement,
3rd plug at 40' with 10 sx cement,
4th plug to circulate rathole with 15 sx cement,
5th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

RECEIVED
STATE CORPORATION COMMISSION
11-19-92
NOV 10 1992

I (did ~~not~~) observe this plugging.

Signed Duane Rankin (TECHNICIAN)

INVOICED
DATE DEC 10 1992
INV. NO. 37056

EFFECTIVE DATE: 11-8-92

State of Kansas

FORM MUST BE SIGNED

NOTICE OF INTENTION TO DRILL 185-22,882

ALL BLANKS MUST BE FILLED

DISTRICT # 1
5617 Yes No

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date November 9, 1992
month day year

Spot NE NW NW Sec 14 Twp 24 S, Rg 15 East West

OPERATOR: License # 5010
Name: Knighton Oil Company, Inc.
Address: 221 South Broadway-#710
City/State/Zip: Wichita, Kansas 67202
Contact Person: Earl M. Knighton, Jr.
Phone: (316) 264-7918

330 feet from South/ North line of Section
990 feet from East/ West line of Section
IS SECTION X REGULAR IRREGULAR?

CONTRACTOR: License #: 5929
Name: Duke Drilling Company, Inc.

(NOTE: Locate well on the Section Plat on Reverse Side)
County: Stafford
Lease Name: Doran Well #: 1
Field Name: Unknown
Is this a Prorated/Spaced Field? yes X no
Target Formation(s): Arbuckle
Nearest lease or unit boundary: 330
Ground Surface Elevation: 2908 feet MSL
Water well within one-quarter mile: yes X no
Public water supply well within one mile: yes X no
Depth to bottom of fresh water: 100
Depth to bottom of usable water: 295
Surface Pipe by Alternate: X 1 2
Length of Surface Pipe Planned to be set: 280
Length of Conductor pipe required: N/A
Projected Total Depth: 4160
Formation at Total Depth: Arbuckle
Water Source for Drilling Operations:
X well farm pond other
DWR Permit #:
Will Cores Be Taken? yes X no
If yes, proposed zone:
320' Alt. I Req.

Well Drilled For: Well Class: Type Equipment:
X Oil ... Enh Rec ... Infield X Mud Rotary
X Gas ... Storage ... Pool Ext. ... Air Rotary
... OWD ... Disposal X Wildcat ... Cable
... Seismic: ... # of Holes ... Other
If OWD: old well information as follows:
Operator:
Well Name:
Comp. Date: Old Total Depth
Directional, Deviated or Horizontal wellbore? yes X no
If yes, true vertical depth:
Bottom Hole Location:

AFFIDAVIT

Exp. 5/3/93

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.

Pusher dyle
SPUD DATE 11-08-92 INIT. CP
LENGTH SURFACE PLANNED 280
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.
RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 7 1/2 @ 3 1/2 CONDUCTOR
ANHYDRITE T- B- ELEVATION
TD FORMATION
RAN PIPE @ DV TOOL ALT II DONE
SX SX Y N
Arbuckle Plug @ Ft. W/ SX
Hug./Council @ Ft. W/ SX
Anhydrite Base @ Ft. W/ SX
1/2 Base Anyh. @ Ft. W/ SX
1/2, 1/2 Plug @ Ft. W/ SX
Bottom Surface @ Ft. W/ SX
40' Plug @ Ft. W/ SX
RAT HOLE CIRC/W SX MOUSE HOLE W/ SX
WATER WELL SX (Irr. Well Pond
Hauling
TECHNICIAN DATE
TYPE OF CEMENT
STARTING TIME NOV (AM/PM) DATE
COMPLETION TIME (AM/PM) DATE
CEMENT COMPANY

RECEIVED
OPERATION COMMISSION

NOV 9 1992