

7-24-87 15-185-00954-0000

To: 1 120006
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Drill Date 6/4/54

NE NE NE, SEC. 14, T 24 S, R 15 W/X
4950 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5921

Lease Name Isern Well # 1

Operator: Jon Carroll
Name &

County Stafford 138.78

Address P.O. Box 1987

Well Total Depth 4270 feet

Great Bend, KS 67530

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 215

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address Box 768, Great Bend, KS 67530

Company to plug at: Hour: 2:30 p.m. Day: 24 Month: 7 Year: 19 87

Plugging proposal received from Mike Gomez

(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 5 1/2" at 4252' Perfs at 4126-46'

1st plug sand back to 4075' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 5 sx hulls and 130 sx lite cement.

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 3:30 p.m. Day: 24 Month: 7 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 4075' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped through 8 5/8" surface casing with 500 lbs. hulls and 130 sx lite cement.

0 psi pressure.

STATE CORPORATION COMMISSION
AUG 3 1987
8-3-87
Wichita, Kansas

Remarks: Used lite cement by Allied. Recovered 3027' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
observe this plugging.

Signed Duane Rankin (TECHNICIAN)

DATE 8-5-87

INV. NO. 17696