

1030220

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 185-22,025-0000

SE SE NW, SEC. 13, T 24 S, R 15 W/E  
600 feet from N/S section line

330 feet from N/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6033

Lease Name English-Reid Well # 6

Operator: Murfin Drilling Co.

County Stafford

Name & Address 250 North Water, Suite 300

Well Total Depth 4370 <sup>142.03</sup> feet

Wichita, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 599

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Murfin Drilling Co. License Number 6033

Address 250 North Water, Suite 300, Wichita, KS 67202

Company to plug at: Hour: 9:00 am Day: 17 Month: June Year: 1984

Plugging proposal received from Marvin Jullian

(company name) Murfin (phone) 316-267-3241

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 960' with 50 sx cement

2nd plug at 630' with 40 sx cement  
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 10 sx cement. Plug water well with 5 sx cement

Plugging Proposal Received by Steve Belmont  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 11:30 am Day: 17 Month: June Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 960' with 50 sx cement, 2nd plug at 630' with 40 sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10

sx cement, 5th plug to circulate rat hole with 10 sx cement. Plugged water well with 5

sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

JUL 06 1984

7-6-84  
CONSERVATION DIVISION

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied.  
(If additional description is necessary, use BACK of this form)

INVOICED

(operator or lic. holder) observe this plugging.

DATE 7-12-84

Signed Steve Belmont  
(TECHNICIAN)

INV. NO. 2422