

120182

12-13

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-185-20,969-0000

NE SE NW, SEC. 12, T 24 S, R 15 W/E

3630 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5015

Lease Name Suiter Well # 2

Operator: Hellar Drilling Inc.
Name & Address: 711 Petroleum Building
Wichita, KS 67202

County Stafford 130.78

Well Total Depth 4024 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 276

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Rockhold Engineering, Inc. License Number 5111

Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 10 a.m. Day: 13 Month: 12 Year: 1988

Plugging proposal received from Jim Rockhold

(company name) Rockhold Engineering, Inc. (phone) 316-792-2506

were: 5 1/2" at 4204' cemented with 125 sx cement Perfs at 4047-50' Elevation 1894' GL

1st plug sand back to 3990' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 5 sx hulls, 20 sx gel, release wiper plug and pump 150 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

DEC 16 1988

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operation Extended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11 a.m. Day: 13 Month: 12 Year: 1988

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3990' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 350 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 150 lbs. hulls and 100 sx cement.

Pumping pressure 0-400 psi and shut in 150 psi.

Remarks: Used 60/40 Pozmix 6% gel by HOWCO. Recovered 1656' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED (could not observe this plugging.)

DATE DEC 19 1988

Signed Dean Rankin (TECHNICIAN)

INV. NO. 23395