

To: 1 120181
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5015

Operator: Hellar Drilling Company, Inc.

Name

Address 711 Petroleum Building

Wichita, KS 67202

Abandoned Oil Well ☒ Gas Well ☐ Input Well ☐ SWD Well ☐ D&A ☐

Other well as hereinafter indicated

Plugging Contractor Rockhold Engineering, Inc.

Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 8:30 a.m. Day: 13 Month: 12 Year: 1988

Plugging proposal received from Jim Rockhold

(company name) Rockhold Engineering, Inc. (phone) 316-792-2506

were: 5½" at 4092' cement w/150 sx cement Top Perf at 4081'

1st plug sand back to 4030' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls and 100 sx cement.

Plugging Proposal Received by Mike Spain

(TECHNICIAN)

Plugging Operations attended by Agent?: All ☒ Part ☐ None ☐

Operations Completed: Hour: 9:30 a.m. Day: 13 Month: 12 Year: 1988

ACTUAL PLUGGING REPORT 1st plug sanded 5½" casing back to 4030' and dumped 5 sx cement

on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 350 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 150 lbs. hulls and 100 sx cement.

Pumping pressure 0-550 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by HOWCO. Recovered 2156' of 5½" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED (d/d / XXXXXX) observe this plugging.

DATE DEC 19 1988

Signed

Deane Rankin
(TECHNICIAN)

NO. 23394

NO. 23394