

To: **120911**
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

3-29 API NUMBER **15-185-20755-0000** **194**
15- Spudded 7/21/77

N/2 NW SW, SEC. 12, T 7 S, R 15 W
2310 feet from S section 11-
4620 feet from E section 11-

TECHNICIAN'S PLUGGING REPORT

Operator License # 3911
Operator: RAMA Operating Co., Inc.
Name: _____
Address P.O. Box 159
Stafford, KS 67578

Lease Name Devore Well # 1
County Stafford
Well Total Depth 4230 127.47 ft
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 262

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 2:45 p.m. Day: 29 Month: 3 Year: 1994

Plugging proposal received from Mike Kelso
(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

vers: 5 1/2" at 4198' w/150 sx cement, PBTD 4170', Perfs at 3787-90, 4051-55'
1st plug sand back to 3730' and dump 5 sx cement on top of sand through bailer,
2nd plug pump into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx
gel, 100 lbs. hulls, and 125 sx cement.

Plugging Proposal Received by Case Morris
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 4:45 p.m. Day: 29 Month: 3 Year: 1994

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3730' and dumped 5 sx cement on
top of sand through bailer,
2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10
sx gel, 100 lbs. hulls and 125 sx cement. Plate and 5 1/2" collar welded in 8 5/8" surface casing.
Pumping pressure 0-350 psi and shut in 50 psi.

RECEIVED
STATE CORPORATION COMMISSION
4-1-94
APR 01 1994
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2400' of 5 1/2" casing.
(If additional description is necessary, use BACK of this report to observe this plugging.)

INVOICED

DATE APR 8 1994

Signed Case Morris
(TECHNICIAN)

INV. NO. 40297