

To: 1-120267
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

6-19 90
API NUMBER 15-185-20,780-0000
SE. NE. NE, SEC. 28, T. 24 S, R. 13 W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 5673
Operator: W.L. Kirkman, Inc.
Name & Address P.O. Box 782290
Wichita, KS 67278-2290

4290 feet from S section line
330 feet from E section line
Lease Name Curtis Well # 1
County Stafford 105.30
Well Total Depth 3240 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 464

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 4 p.m. Day: 19 Month: 6 Year: 19 89

Plugging proposal received from Millard Kelso
(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 4 1/2" at 2016' Perfs at 1876-80' Elevation 1929' GL

1st plug pump 1 sx hulls and 25 sx cement,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5 p.m. Day: 19 Month: 6 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug pumped 100 lbs. hulls and 25 sx cement and pushed plug to 1800',

2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Pumping pressure 0-500 psi and shut in 200 psi.

RECEIVED
STATE CORPORATION COMMISSION

JUN 20 1989

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1400' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 6-27-89

INV. NO. 25128
6-19

Signed Steve Raskin
(TECHNICIAN)