

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-10992-00-00
Spot: CSWSENV Sec/Twnshp/Rge: 28-24S-13W
2970 feet from S Section Line, 3630 feet from E Section Line
Lease/Unit Name: TOLAND Well Number: 1
County: STAFFORD Total Vertical Depth: 4178 feet

Operator License No.: 3493
Op Name: FISHER, REGINALD D.
Address: 110 N. EXCHANGE
ST. JOHN, KS 67576

Conductor Pipe: Size feet: 8/35.79
Surface Casing: Size 8.625 feet: 226 WITH 200 SX CMT
Production: Size 5.5 feet: 4173 WITH 150 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 08/12/2002 10:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2537

Proposed
Plugging
Method:

SAND TO 3750' & 5 SX CMT. RUN TUBING TO 850' & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 08/12/2002 12:40 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PBTD 3880'. PERFS AT 3757-60, 3768-70, 3775-76, 3795-03, 3822-30, & 3834-36'. LEFT 2 JOINTS OF 2 7/8" TUBING & INSERT PUMP IN BOTTOM OF WELL. SANDED TO 3750' & 5 SX CMT WITH DUMP BAILER. RAN TUBING TO 850'. CIRCULATED CMT TO SURFACE WITH 390 SX CMT. PULLED TUBING OUT OF HOLE. TOPPED OFF HOLE WITH 5 SX CMT.

RECEIVED
AUG 19 2002
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 300' OF 5 1/2" CASING.

Plugged through: TBG

District: 01

Signed

Richard W. Lacey

(TECHNICIAN)

INVOICED

AUG 15 2002

DATE

8-19-02

TRK. NO.

2003060236 AP

Form CP-23