

To: 1 121112  
STATE-CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15-185-22,705-0000  
C SW SW, SEC. 28, T 24 S, R 13 W/E  
1320 feet from S section line  
3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5538  
Operator: Tom Kat LTD  
Name & Address: P.O. Box 1471  
Great Bend, KS 67530

Lease Name Weber-Knoche Well # 1  
County Stafford  
Well Total Depth 4200 136.50 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 315

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Mike's Testing & Salvage Inc. License Number 31529  
Address P.O. Box 209, Chase, KS 67524

Company to plug at: Hour: 3:30 p.m. Day: 1 Month: 4 Year: 19 96

Plugging proposal received from Mike Kelso  
(company name) Mike's Testing & Salvage Inc. (phone) 316-938-2943

work: 5 1/2" at 4148' w/150 sx cement, PBSD 4065', Perfs at 3986-4010'  
1st plug sand back to 3930' and dump 5 sx cement on top of sand through bailer,  
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, release 8 5/8" wiper plug and pump 125 sx cement.

STATE RECEIVED  
FROM COMMISSION

APR 4 1996  
4-4-96

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 4:30 p.m. Day: 1 Month: 4 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3930' and dumped 5 sx cement on top of sand through bailer,  
2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.  
Pumping pressure 0-500 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2000' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE APR 22 1996

INV. NO. 45377

Signed *Steve Pfeifer*  
(TECHNICIAN)