

TO: \*  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-097-20546-00-00  
Spot: CNESE Sec/Twnshp/Rge: 2-27S-16W  
1980 feet from S Section Line, 660 feet from E Section Line  
Lease/Unit Name: EMMA Well Number: 1  
County: KIOWA Total Vertical Depth: 4610 feet

Operator License No.: 5364  
Op Name: BEREN CORPORATION  
Address: P.O. BOX 20380  
WICHITA, KS 67208

Conductor Pipe: Size feet: 149.83  
Surface Casing: Size 8.625 feet: 390 WITH 300 SX CMT  
Production: Size 4.5 feet: 4614 WITH 250 SX CMT  
Liner: Size feet:

Well Type: GAS UIC Docket No: Date/Time to Plug: 11/19/2002 1:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: PUMP BOTTOM WITH 50 SX CMT & 400# HULLS. PLUG AT 1050' WITH 50 SX CMT. PLUG AT 420' WITH 50 SX CMT. PLUG AT 0-40' WITH 10 SX CMT. USE 10 SX GEL FOR SPACER.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 11/19/2002 5:20 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:


PERFS AT 4028-4486 MULTIPLE SETS. PUMPED 55 SX COMMON CMT & 400# HULLS DOWN 4 1/2" DISPLACING IT TO 3940'. PUMPED PLUGS DOWN CASING. 1ST PLUG AT 1050' WITH 10 SX GEL - 50 SX CMT WITH 100# HULLS. 2ND PLUG AT 420' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

RECEIVED  
NOV 27 2002 11-27-2002  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2430' OF 4 1/2" CASING.

Plugged through: CSG

District: 01



Signed Richard W. Lacey  
(TECHNICIAN)

INVOICED  
DATE 12-2-02  
INV. NO. 2003060876

Form GP-2/3