

To: 1 041269  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202  
10-23

API NUMBER 15-047-21,327-00-01

S/2 S/2 SW, SEC. 17, T 24 S, R 17 W/2E

330 feet from S section line  
3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5056

Lease Name J.H. Cross Well # 1-17

Operator: F.G. Holl Company, L.L.C.  
Name & Address P.O. Box 780167  
Wichita, KS 67278-0167

County Edwards 148.33

Well Total Depth 4564 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 309

Abandoned Oil Well  Gas Well  Input Well  SWD Well  O&A

Other well as hereinafter indicated

Plugging Contractor Pratt Well Service License Number 5893

Address P.O.Box 847, Pratt, KS 67124

Company to plug at: Hour: 12 p.m. Day: 23 Month: 10 Year: 19 97

Plugging proposal received from Donnie Fisher

(company name) Pratt Well Service (phone) 316-672-2531

Work: 4 1/2" at 4557' w/225 sx cement, CIBP at 4360', Perfs at 4380-91, 4102-12, 4295-97'

1st plug sand back to 4050' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8"

wiper plug and pump 150 sx cement.

10-28-97

Plugging Proposal Received by Scott Alberg (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 12:30 p.m. Day: 23 Month: 10 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug sanded back to 4030' and dumped 4 sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 500 psi and shut in 175 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 1827' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE OCT 29 1997

Signed Stephen J. Pfeifer (TECHNICIAN)

INV. NO. 49372