

1 030621

15-047-50004-0001

API NUMBER 15- OWWO Comp. 1974

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C SE NW, SEC. 17, T 24 S, R 17 ^{XX} _{W/E}

3300 feet from S section line

3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056

Lease Name Lovette Well # 1-17

Operator: F. G. Holl

County Edwards

Name &

Address 6427 East Kellogg

Well Total Depth 4450 feet

Wichita, KS 67207

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 253

Abandoned Oil Well ☒ Gas Well ☒ Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 2:00 pm Day: 17 Month: December Year: 19 85

Plugging proposal received from Vernon Duntz

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" at 4449' PBTB 4409' Perfs at 4370-76'

1st plug pump 1 sack hulls and 30 sx cement to bottom and push plug to 4000'

2nd plug squeeze well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,

release 8 5/8" rubber plug and pump 130 sx cement.

Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)Plugging Operations attended by Agent?: All ☒ Part None

Operations Completed: Hour: 2:40 pm Day: 17 Month: December Year: 19 85

ACTUAL PLUGGING REPORT 1st plug pumped 1 sack hulls and 30 sx cement to bottom and

pushed plug to 4000'. 2nd plug squeezed well with 2 sx hulls, 15 sx gel, 50 sx cement,

10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 130 sx cement.

Maximum pressure 700 psi and shut in 200 psi

Remarks: Recovered 2285' 4 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)I did observe this plugging. RECEIVED
STATE CORPORATION COMMISSION

Signed

Steve Duntz (Sns)
(TECHNICIAN)

DATE 12-31-85

DEC 27 1985

INV. NO. 11785

CONSERVATION DIVISION
Wichita, KansasFORM CP-2/3
Rev. 01-84