

1 110163

7-27

293

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 047-21,358-0000
165' N of
SE NE SW, SEC. 17, T 24 S, R 17 W/EX
1815 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056
Operator: F.G. Holl Company
Name & Address: P.O. Box 780167
Wichita, KS 67278-0167

Lease Name J.H. Cross Well # 2-17
County Edwards 147.71
Well Total Depth 4545 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 321

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Sterling Drilling Company License Number 5142

Address P.O. Box 129, Sterling, KS 67579

Company to plug at: Hour: 12 a.m. Day: 27 Month: 7 Year: 19 90

Plugging proposal received from Vaughn Thompson

(company name) Sterling Drilling Company (phone) 316-278-2131
Elevation 2116 GL

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1168-79'
1st plug at 1180' with 40 sx cement, 2nd plug at 600' with 40 sx cement,
3rd plug at 350' with 50 sx cement, 4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement,
6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by James R. Kapp
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 1:30 a.m. Day: 27 Month: 7 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 1180' with 50 sx cement,
2nd plug at 600' with 40 sx cement,
3rd plug at 350' with 50 sx cement,
4th plug at 60' with 15 sx cement,
5th plug to circulate rathole with 15 sx cement,
6th plug to circulate mousehole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
JUL 30 1990 7-30-90
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.
(If additional description is necessary, use BACK of this form.)

INVOICED

(did not) observe this plugging.

DATE 8-2-90
INV. NO. 28861
7-27

Signed James R. Kapp
(TECHNICIAN)