

15-151-10235-0001

1041316

TO: STATE CORPORATION COMMISSION 9-28 API NUMBER DRILLED IN 1953
 NW SW SW SEC. 18, T 27 S, R 12 W

CONSERVATION DIVISION - PLUGGING SECTION 990 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 4950 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME SICU (JUSTICE) WELL # 19

TECHNICIAN'S PLUGGING REPORT COUNTY PRATT 141.83

OPERATOR LICENSE # 31739 WELL TOTAL DEPTH 4364 FEET

OPERATOR: IUKA-CARMI DEVELOPMENT, LLC PRODUCTION CSG: SIZE 5 1/2 " FEET 4363

NAME AND PO BOX 847 SURFACE CASING: SIZE 8 5/8 " FEET 768

ADDRESS PRATT, KS67124-0847

ABANDONED OIL WELL GAS WELL INPUT WELL INJ WELL E-8202 D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR PRATT WELL SERVICE LICENSE NUMBER 5893

ADDRESS PO BOX 847, PRATT, KS 67124-0847

COMPANY TO PLUG AT: HOUR: 1:00 PM DAY: 28 MONTH: 09 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM GERALD INSLEE

(COMPANY NAME) PRATT WELL SERVICE (PHONE) 316-672-2531

WERE: PERFS AT 4292-4353

1ST PLUG SET CIBP @ 4222' AND PUT 2 SX CEMENT ON TOP OF CIBP THRU DUMP BAILER.

LOADED HOLE WITH DRILLING MUD. SPOTTED PLUGS THRU 2 7/8" TUBING.

2ND PLUG AT 805' WITH 40 SX CEMENT. 3RD PLUG AT 310' WITH 40 SX CEMENT.

4TH PLUG AT 60' WITH 20 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY STEVE PFEIFER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 3:00 PM DAY: 28 MONTH: 09 YEAR: 1998

ACTUAL PLUGGING REPORT

1ST PLUG SET CIBP AT 4222' AND PUT 2 SX CEMENT ON TOP OF CIBP THRU DUMP BAILER.

LOADED HOLE WITH DRILLING MUD. SPOTTED PLUGS THRU 2 7/8" TUBING.

2ND PLUG AT 805' WITH 50 SX CEMENT. 3RD PLUG AT 310' WITH 40 SX CEMENT.

4TH PLUG AT 60' WITH 20 SX CEMENT.

REMARKS: USED COMMON CEMENT WITH 4%CC BY UNITED. RECOVERED 1850' OF 5 1/2" CASING.
 (IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Stephen J. Pfeifer
 (TECHNICIAN) FORM CP-2/3

10-15-98
 60116