

1 010199

15451-10229-0001

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- N/A D-3653

NW SW SE, SEC. 18, T 27 S, R 12 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 4742

Lease Name Seidel "A" Well # 1

Operator: Texaco Inc. for Texaco Producing Inc.

County Pratt

Name &

Address Box 2420

Well Total Depth 4780 feet

Tulsa, OK 74102

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 833

Abandoned Oil Well Gas Well Input Well SWD Well X D&A

Other well as hereinafter indicated

Plugging Contractor Pratt Well Service Inc. License Number 5893

Address Box 847, Pratt, KS 67124

Company to plug at: Hour: 10:45 a.m. Day: 9 Month: 1 Year: 19 87

Plugging proposal received from John Luther

(company name) Pratt Well Service (phone) 316-672-2531

were: 5 1/2" at 4390' Open hole 4390-4780' 3" Fiberglass tubing parted at 244' top fish found at 1510'

Fill 5 1/2" casing with lite cement, then try to recover tubing. If it sticks, just leave it.

Pump 1 1/2 times fill volume down 8 5/8" annulus.

Plugging Proposal Received by Don Ubel

(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 12:30 p.m. Day: 9 Month: 1 Year: 19 87

ACTUAL PLUGGING REPORT Pumped cement through tubing from 1520' (TD) to surface.

Took 82 SX cement. Pumped 30 sx cement down back side. 300 lbs. pressure.

1-14-1987

STATE CORPORATION COMMISSION

Remarks: Used Econo-lite by Halliburton.

JAN 14 1987

(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

INVOICED

observe this plugging.

DATE 1-15-87

Signed

(TECHNICIAN)

INV. NO. 15916

FEB 10 1987

FORM CP-2/3
Rev. 01-84