

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-173-20,406-0000

SEC 33, T 29S, R 2 W

FEET FROM N/S SECTION LINE

FEET FROM W/E SECTION LINE

TECHNICIAN'S PLUGGING REPORT

OPERATOR LICENSE # 5033

LEASE NAME Daley WELL # 1

OPERATOR: Crowe Dwg. Co.
NAME & ADDRESS 1732 E's, St. Bk. Bldg.
Wichita, Ks. 67202

COUNTY Sedgwick

WELL TOTAL DEPTH 3220 104.65 FEET

CONDUCTOR PIPE: SIZE - FEET -

SURFACE CASING: SIZE 8 7/8 FEET 448

ABANDONED OIL WELL _____ GAS WELL ☒ INPUT WELL _____ SWD WELL _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR B & S well service LICENSE NUMBER 6013

ADDRESS Winfield, Ks.

COMPANY TO PLUG AT: HOUR: _____ DAY: 6 MONTH: Feb. YEAR: 19 84

PLUGGING PROPOSAL RECEIVED FROM Bob Sutters

(COMPANY NAME) B & S (PHONE) _____

WERE: 4 1/2" casing set @ 2718. Perf. @ 2677-81

Top of Cement on back side 2395.

Sand back to 2627 & Dump 45X.

Shot & pulled 2320.

PLUGGING PROPOSAL RECEIVED BY

Glenn Ward
(TECHNICIAN)PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL ☒ PART _____ NONE _____

OPERATIONS COMPLETED: HOUR: 4:00 PM DAY: 11 MONTH: Feb. YEAR: 19 84

ACTUAL PLUGGING REPORT Top plug as follows

Pump 65X gel & 35X Huller & 150 SX class "A"
Cement down 8 7/8 surface thro 8 7/8 swage
mix. PSI 500 close in @ 200 PSI.

REMARKS: united ticket # 5601

I (DID) DID NOT) OBSERVE THIS PLUGGING.

INVOICED

DATE 2-15-84

INV. NO. 0223

2-11

RECEIVED
STATE CORPORATION COMMISSION

FEB 14 1984

CONSERVATION DIVISION
Wichita, Kansas

SIGNED

Glenn Ward
(TECHNICIAN)FORM CP-2/3
REV. 6-83