

FEB 21 1984

CONSERVATION DIVISION
Wichita, Kansas

2-21-1984

2 050066

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-173-20,524-0000

NE/SW/SW SEC. 33, T29S, R2W

TECHNICIAN'S PLUGGING REPORT

OPERATOR LICENSE # 5033

OPERATOR: Crowe Drlg. Co. Inc.
NAME & ADDRESS 1732 HS. ST. BK. Bldg.
Wichita, KS. 67202

FEET FROM N/S SECTION LINE

FEET FROM W/E SECTION LINE

LEASE NAME Whitesell WELL # 1

COUNTY Sedgwick

WELL TOTAL DEPTH 2684 87.23 FEET

CONDUCTOR PIPE: SIZE FEET

SURFACE CASING: SIZE 8 7/8 FEET 479

ABANDONED OIL WELL GAS WELL ☒ INPUT WELL SWD WELL D&A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR B+S LICENSE NUMBER 6013

ADDRESS Winfield, KS.

COMPANY TO PLUG AT: HOUR: 1:00 PM DAY: 14 MONTH: Feb. YEAR: 19 84

PLUGGING PROPOSAL RECEIVED FROM Jim Parker

(COMPANY NAME) (PHONE)

WERE: send back to 2650 & Dump 4 SK. Cement

shot & Pull Pipe

Pump 175 SK Cement

Down Surface pipe & close in

RECEIVED 2-21-84

STATE CORPORATION COMMISSION

PLUGGING PROPOSAL RECEIVED BY Glenn J. Ward
(TECHNICIAN)

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL ☒ PART NONE

OPERATIONS COMPLETED: HOUR: 2: PM DAY: 14 MONTH: Feb. YEAR: 19 84

ACTUAL PLUGGING REPORT 4 1/2" Casing was set @ 2680. open

hole from 2680-84. sanded back to 2650

& Dump 4 SK. Cement. shot & pulled 2328 ft. of

Casing.

pumped Down Casing thru 8 5/8 Swage

6 SK. del 3 SK. Hulle & 175 SK. Class "A" Cement

REMARKS 3% CC. 1774 PSI. 2000. closed in 200 psi

united ticket # 5604

(DID) DID NOT) OBSERVE THIS PLUGGING.

SIGNED Glenn J. Ward
(TECHNICIAN)

INVOICED

DATE 2-23-84

INV. NO. 0329

2-14

FORM CP-2/3
REV. 6-83