

To: 1020134  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

4-14-88 102 R  
API NUMBER 15- 025-21,008-0000

TECHNICIAN'S PLUGGING REPORT

Operator License # 3692

Operator: American United Petroleum Inc.

Name &

Address 216000 Oxnard Street

Woodlawn Hills, CA

Lease Name Koehn Well # 1

County Clark

Well Total Depth 4691 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 537

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Eagle Drilling License Number 5380

Address Box 8609, Wichita, KS 67208

Company to plug at: Hour: 4 p.m. Day: 14 Month: 4 Year: 1988

Plugging proposal received from Butch Steinert

(company name) Eagle Drilling (phone) 316-945-9935

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1403'

1st plug at 1440' with 50 sx cement,

2nd plug at 567' with 40 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement, 5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 6 p.m. Day: 14 Month: 4 Year: 1988

ACTUAL PLUGGING REPORT 1st plug at 1440' with 50 sx cement,

2nd plug at 567' with 40 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. (If additional description is necessary, use BACK of this form.)

INVOICED  
(If copy is not observed this plugging.

DATE 4-25-88

INV. NO. 20431

CONSERVATION DIVISION  
Wichita, Kansas

Glenn R Barlow (TECHNICIAN)