


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Stafford County, Sec. 36 Twp. 24 Rge. 14 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines _____

Lease Owner C. NE. NE
W. L. Kirkman, Inc.
Lease Name Mackley #1 Well No. _____
Office Address Pratt, Kansas 67124
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plat

Date Well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 2/21/77 _____ 19____
Plugging completed 2/23/77 _____ 19____
Reason for abandonment of well or producing formation
depleted.

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Metz
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 1941
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	224	none
				5 1/2	1911	1557'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded to 1900' and ran 5 sacks cement. Shot pipe at 1545', pulled 49 joints. Squeezed hole with 3 sacks hulls, 15 sacks gel, released plug and displaced with 100 sacks 50-50 pozmix.

PLUGGING COMPLETE.

FEB 25 1977

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING
CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
R. DARRELL KELSO (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of Feb., 19 77

Margaret Melcher
Notary Public.

My commission expires _____



DRILLERS LOGMACKLEY #1

CASING RECORD:
8 5/8" at 224'
w/200 Sx. Cement

OPERATOR: Wayne L. Kirkman

DESCRIPTION:

CONTRACTOR: Search Drilling Co.

C NE NE,
Sec.36-24S-14W
Stafford County,
KansasTOTAL DEPTH:

COMMENCED: March 15, 1974

1941'

COMPLETED: March 16, 1974

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil and Sand	0	140	
Shale	140	227	
Redbed	227	492	
Redbed and Shale	492	1250	
Shale and Sand	1250	1710	
Lime and Shale	1710	1800	
Lime and Shale	1800	1941	Run 62 joints used 14# - 5 1/2". Cemented with 75 sacks 60-40 pozmix.

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SEARCH DRILLING COMPANY

Clarence Michael
Clarence Michael

Subscribed and sworn to before me this 21st. day of March, 1974.

My Commission expires:
February 19, 1977

Maxine Dressen
Maxine Dressen

RECEIVED
STATE CORPORATION COMMISSION

FEB 15 1977

CONSERVATION DIVISION
Wichita, Kansas