

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.--82-3-117

API NUMBER 15-185-21940-0006

LEASE NAME Waters

WELL NUMBER A-1

 Ft. from S Section Line

 Ft. from E Section Line
NW NE NW

SEC. 32 TWP. 24S RGE. 14W (E) or (W)

COUNTY Stafford

Date Well Completed

Plugging Commenced 5-26-87

Plugging Completed 6-3-87

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Texas Energies, Inc.

ADDRESS P.O. Box 947
Pratt, Kansas 67124

PHONE# (316) 672-7514 OPERATORS LICENSE NO. 5087

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dist. #1 Dodge City, Kansas

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4410'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	307'	none
				4-1/2"	4386'	2730'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged off bottom with sand to 4060' and 4 sacks cement. Shot pipe @3539', 3136', 2932', 2730', pulled a total of 69 joints of 4-1/2" casing. Plugged surface with 2 hulls, 10 gel, 50 cement, 15 gel, 1 hull, plug and 125 cement, 60/40 pos, 6% gel.
Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050'

Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso, Vice-President (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) P.O. Box 347
Chase, Kansas 67524


SUBSCRIBED AND SWORN TO before me this 4th day of June, 19 87

Jane Hoover
Notary Public
STATE CORPORATION COMMISSION


My Commission Expires:



JUN 8 1987 Form CP-4
Revised 07-86
CONSERVATION DIVISION
Wichita, Kansas



ACOUSTIC CEMENT BOND
VCL. GAMMA RAY



FILE NO. _____

API NO. _____

COMPANY TEXAS ENERGY

WELL ~~No. 1 WATERS A~~

FIELD SEMI WILD CAT

COUNTY STAFFORD STATE KANSAS

LOCATION: NW-NE-NW

Other Services
PERF

SEC 32 TWP 24s RGE 14W1

Permanent Datum 6.6 Elev. 1985

Log Measured from 11.03 10 Ft. Above Permanent Datum Elev. 1997

Drilling Measured from 11.03 DF 1995

GL 1985

Date	<u>5-7-84</u>		
Run No.	<u>ONE</u>		
Service Order	<u>42026</u>		
Depth--Driller	<u>4410</u>		
Depth--Logger	<u>4310</u>		
Bottom Logged Interval	<u>4307</u>		
Top Logged Interval	<u>3246</u>		
Type Fluid in Hole	<u>WATER</u>		
Salinity Ppm Cl.	<u>-</u>		
pH and Fluid Loss	<u>-</u>		
Density Lb./Gal.	<u>-</u>	cc	cc
Level	<u>FULL</u>		
Max. Rec. Temp. Deg. F	<u>-</u>		
Opr. Rig Time	<u>1.5 HR.</u>		
Recorded By	<u>WHL BARN</u>		
Witnessed By	<u>TED MOFF</u>		

FIELD PRINT

Run No.	Bore Hole Record			Casing Record			
	Bit	From	To	Size	Wt.	From	To
1				4 1/2	-	SURF	T.D.

I HANK
YOU!!!