

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

Stafford

County. Sec. 34 Twp. 24 Rge. (E) 14 (W)

Location as "NE/CNW&SW&" or footage from lines NE NE NE

Lease Owner Aylward Drilling Company

Lease Name Kachelman "F" Well No. 1

Office Address 813 First National Bank Bldg. - Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) D&A

Date well completed January 29 1962

Application for plugging filed January 29 1962

Application for plugging approved January 29 1962


Plugging commenced January 29 1962

Plugging completed January 29 1962

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot

Producing formation Depth to top Bottom Total Depth of Well 4315 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	250'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy mud to 240'  
Plug at 240' with 20 sacks cement and 1/3 sack hulls  
Heavy mud to 35'  
Plug at 35' with 10 sacks cement and 1/3 sack hulls  
2 sacks cement in rathole.

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 27 1962  
CONSERVATION DIVISION  
Wichita, Kansas  
6-27-1962

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Company tools  
Address

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Charles D. Williams (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Charles D. Williams  
813 1st Nat'l Bank Bldg. - Wichita 2, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 1st day of February, 1962

My commission expires December 11, 1965

Duane Jessup  
DUANE JESSUP Notary Public.



KACHELMAN "F" NO. 1

Casing Record: 8 5/8" - 250'  
 Company: Aylward Drilling Company  
 Contractor: Aylward Drilling Company  
 Commenced: January 16, 1962  
 Completed: January 29, 1962  
 Location: NE NE NE  
 Sec. 34-24-14W  
 Stafford County, Kansas  
 Elevation: 1944 K.B.

	<u>From</u>	<u>To</u>	<u>Remarks</u>
Sand	0	131	Set 8 5/8" surface pipe @ 250' w/260 sacks cement.
Sand & Clay	131	150	
Blue Shale & Shells	150	180	Geological Tops:
Red Bed	180	615	
Shale & Shells	615	855	Haebner 3498
Anhydrite	855	878	Toronto 3517
Shale & Shells	878	1140	Douglas 3537
Sand	1140	1260	Lansing 3664
Shale	1260	1280	B/Kan. City 3941
Shale & Shells	1280	1800	Conglomerate 4025
Shale & Lime	1800	1930	Mississippian 4062
Lime & Shale	1930	2085	Viola 4140
Lime	2085	2155	Simpson Shale 4229
Lime & Shale	2155	2350	Simpson Sand 4241
Shale & Lime	2350	3470	Arbuckle 4293
Lime	3470	3555	
Lime & Shale	3555	3820	
Lime	3820	3965	DST 4026-46 Open 1 hr.
Lime & Shale	3965	4046	Rec. 10' mud
Shale & Chert	4046	4100	IBHP 62#/20" - FBHP 26#/20"
Lime & Shale	4100	4145	FP 14#-20#.
Lime, Shale & Chert	4145	4241	
Lime & Shale	4241	4295	DST 4063-4100 Open 1 hr.
Lime	4295	4315 T.D.	Rec. 15' mud.
			IBHP 119#/20" - FBHP 108#/20"
			FP 0.

STATE OF KANSAS  
 STATE CORPORATION COMMISSION

JUN 27 1962

CONSERVATION DIVISION  
 Wichita, Kansas

D & A

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

*Charles D. Williams*

Subscribed and sworn to before me this 31st day of January, 1962

*Duane Jessup*  
 DUANE JESSUP Notary Public

My commission expires December 11, 1965