


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

## WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Stafford County. Sec. 1 Twp. 24 S Rge. 15W (E) (W)

Location as "NE/CNW&amp;SW" or footage from lines SE NW SE

Lease Owner Welch &amp; Olsson Drilling Co. Inc.

Lease Name English Well No. 1

Office Address 1017 Union National Bank Bldg. Wichita, Kansas.

Character of Well (completed as Oil, Gas or Dry Hole) D &amp; A

Date well completed July 7, 19 53

Application for plugging filed July 7, 19 53

Application for plugging approved July 7, 19 53

Plugging commenced July 7, 19 53

Plugging completed July 7, 19 53

Reason for abandonment of well or producing formation D &amp; A

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. M. A. Rives, Box 148, Pratt, Kansas.

Producing formation Depth to top Bottom Total Depth of Well 4130' Feet

Show depth and thickness of all water, oil and gas formations.

## OIL, GAS OR WATER RECORDS

## CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE   | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
|           |         |      |    | 8-5/8" | 220'   | None       |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded up to 215' and set wooden plug at 215'. Cemented and displaced 20 sacks cement through drill pipe onto plug at 195'.  
Mudded up to 40' and set second wooden plug. Filled Hole to bottom of well cellar with 10 sacks cement.

RECEIVED

STATE CORPORATION COMMISSION

JUL 20 1956 7-20-53

CONSERVATION DIVISION

Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Welch &amp; Olsson Drilling Co., Inc.

Address 1017 Union Nat'l Bank Bldg., Wichita, Kansas.

STATE OF Kansas, COUNTY OF Sedgwick, ss.

R. E. Welch (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)


1017 Union Nat'l Bank Bldg., Wichita, Kansas.

(Address)

Subscribed and sworn to before me this 10th day of June, 19 53

My commission expires Feb. 27, 1956.

Notary Public.



24-7368-S 3-53-20M

WELL LOG

WELCH &amp; OLSSON DRILLING CO., INC.,

Elevation: 1998 K. B.

CONTRACTOR: Welch &amp; Olsson Drilling Co. Inc.

Commenced Drlg.: 6-24-53

English No. 1

Completed Drlg: 7-7-53

SE NW SE Sec. 1-24S-15W,  
Stafford County, Kansas.

Production: D &amp; A

casing record:

Set 220' of 8-5/8" with 175 sacks.

(Figures indicate bottom of formations)

FORMATIONSDEPTHSFORMATION TOPS

|                |      |                 |              |
|----------------|------|-----------------|--------------|
| Surface Soil   | 15   | Heebner Shale   | 3513' -1515' |
| Sand           | 80   | Brown Lime      | 3650' -1652' |
| Shale          | 161  | Lansing Lime    | 3661' -1663' |
| Pyritized      | 162  | Base of the     |              |
| Shale & Shell  | 220  | Kans. City Lime | 3910' -1912' |
| Red Bed        | 936  | Viola           | 4020' -2022' |
| Anhydrite      | 954  | Simpson Shale   | 4071' -2073' |
| Shale & Shells | 1720 | Arbuckle        | 4116' -2118' |
| Lime & Shale   | 1873 |                 |              |
| Lime           | 1990 |                 |              |
| Shale & Lime   | 2250 |                 |              |
| Shale & Shells | 2320 |                 |              |
| Shale & Lime   | 2545 |                 |              |
| Shale & Shells | 3195 |                 |              |
| Lime & Shale   | 3245 |                 |              |
| Lime           | 3600 |                 |              |
| Shale & Lime   | 3661 |                 |              |
| Lime           | 3915 |                 |              |
| Lime & Shale   | 4010 |                 |              |
| Lime           | 4034 |                 |              |
| Cherty Viola   | 4071 |                 |              |
| Shale          | 4075 |                 |              |
| Lime           | 4130 |                 |              |

STATE OF KANSAS, )

SS:-

SEDGWICK COUNTY, )

RECEIVED  
JUL 23 1953  
REGISTRATION DIVISION  
Topeka, Kansas

I hereby certify that the above is a true and correct copy of Drillers Log of well drilled in the SE NW SE of Section 1, Township 24 South, Range 15 West, Stafford County, Kansas.

WELCH &amp; OLSSON DRILLING COMPANY, INC.,

BY: *W. E. Olsson*

Subscribed and sworn to before me  
this 13th day of July, 1953.

My Commission Expires: Feb. 27, 1956.

*Marcella A. Davis*  
Notary Public

