

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-195-00315-0001

LEASE NAME Smith #1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER _____

SPOT LOCATION SW SW SW

SEC. 16 TWP. 24 RGE. 14 (W) or (W)

COUNTY Stafford

LEASE OPERATOR D.R. Lauck Oil Co., Inc.

Date Well Completed _____

ADDRESS 221 S. Broadeay, Suite 400, Wichita, Ks. 67202

Plugging Commenced 10/24/84

PHONE # (316) 263-8267 OPERATORS LICENSE NO. 5427

Plugging Completed 10/24/84

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom T.D. 4378'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	200'	none
				5 1/2"	4294'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plug job only- No pipe recovery. Ran tubing to 871' & pumped 40 sacks & 200# of hulls. Pull to 671' & pumped 100 sacks cement & 200# hull. Pulled to 210' & 20 sacks cement. Pull rest of tubing. Hooked on to surface & pumped 100 sacks cement & 100# of hulls down annulus. (60/40 poz 2% gel 3% c.e..)
Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050
Address Box 347, Chase, Ks. 67524


STATE OF Kansas COUNTY OF Rice, ss. STATE _____

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 26th day of October, 1984



My Commission expires _____

Irene Hoover
Notary Public

RECORDED
10-29-84
NOT 29 1984
CONSERVATION DIVISION
Wichita, Kansas

D. R. Lauck Oil Company, Inc.

and Sunray Mid-Continent Oil Co.

#1 Jay T. Smith

SW SW SW Sec. 16-24S-14W
Stafford County, Kansas

Commenced: December 1, 1955

Completed: December 16, 1955

Elevation: GR 1973; DF 1976; KB 1978.

Casing Record: 200' 8-5/8" Cemented with 175 sacks.
4294' 5-1/2" Cemented with 125 sacks.

Drillers Log

Tops

Drillers Log	Tops
Sand	155
Shale & Shells	200
Shale, Red Bed & Shells	325
Shale & Shells	380
Sand	440
Red Bed, Shale & Shells	865
Anhydrite	890
Shale & Shells	1050
Salt & Shale	1250
Shale & Shells	1535
Lime	1580
Shale & Shells	1775
Lime & Shale	2915
Shale & Shells	3095
Lime & Shale	3410
Lime	3530
Lime & Shale	3658
Lime	3995
Lime & Shale	4030
Lime	4100
Cherty Lime	4130
Chert & Lime	4260
Lime & Shale	4295
Lime	4301 RTD

Samples	Halliburton
Anhydrite	865+1113
Heebner	3513-1535 3514-1536
Brown Lime	3658-1680 3659-1681
Lansing	3677-1699 3678-1700
B/K.C.	3947-1969 3942-1964
Viola	4135-2157 4130-2152
Simpson Shale	4231-2253 4235-2257
Arbuckle	4295-2317 4293-2315
RTD	4301-2323 4301-2323

DST #1, 4295-4301, open 1 hr.
strong blow thruout. Recovered
960' gas above 1860' free oil.
IFP 100#. FFP 740#. BHP 1310#,
in 20 minutes.

RECEIVED
STATE CORPORATION COMMISSION

SEP 19 1984

CONSERVATION DIVISION
Wichita, Kansas

RECEIVED
STATE CORPORATION COMMISSION

SEP 14 1984

CONSERVATION DIVISION
Wichita, Kansas