


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Stafford County. Sec. 16 Twp. 24S Rge. 14 (~~EXX~~) (W)  
Location as "NE/CNW&SWK" or footage from lines SW SW NE  
Lease Owner D.R. Lauck Oil Company, Inc.  
Lease Name Cotton Well No. 2  
Office Address 301 So. Broadway Wichita 2 Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) dry hole  
Date well completed May 3 19 60  
Application for plugging filed " 19 60  
Application for plugging approved " 19 60  
Plugging commenced " 19 60  
Plugging completed " 19 60  
Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4298 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	233	8 5/8"	233	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Hole filled with mud	4298 -	220
plug	220 -	216
20 sx cement	216 -	176
mud	176 -	35
plug	35 -	31
10 sx cement	31 -	6 bottom of cellar

RECEIVED  
STATE CORPORATION COMMISSION

MAY 17 1960

CONSERVATION DIVISION  
Wichita, Kansas

5-17-1960

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Globe Cementing Company  
Address Great Bend Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
John H. Knightley (employee of owner) ~~owner~~ ~~operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John H. Knightley  
Wichita Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 10 th day of May, 19 60

My commission expires Sept. 14, 1963

Elizabeth Kay  
Notary Public.



D. R. Lauck Oil Company, Inc.

Cotton #2

SW SW NE Sec.16-24S-14W  
Stafford County Kansas

Commenced: April 23, 1960

Completed: May 5, 1960

Casing Record: 233' 8 5/8" cem.with 165 sacks  
Calcium Chloride 3 sax

Elevations: GR 1978; DF 1981; KB 1983

## Drillers Log

## Tops

Clay	30	Heebner	3535-1552	3534-1551
sand	40	Douglas	3574-1591	3574-1591
sand & clay streaks	140	Brown Lime	3677-1694	3677-1694
shale	240	Lansing	3698-1715	3698-1715
Red Bed	250	Base Kansas City	3962-1979	3958-1975
Anhydrite	265	Mississippian	4081-2098	4074-2091
Red Bed	380	Kinderhook	4104-2121	4097-2114
sand	435	Viola	4178-2195	4178-2195
Red Bed	912	Simpson	4234-2251	4240-2257
Anhydrite	940	Arbuckle	4293-2310	4293-2310
Shale, shells & red bed	1460			
shale & shells	1770	Rotary Total Depth	4298-2315	4298-2315
shale & Lime	1800			
Anhydrite	1975	DST #1 (M) 4179-4190 open 30 min. weak blow		
shale & Lime	2020	v 10 minutes; recovered 15' mud;		
shale, Lime & sand	2050	flow pressures 22-33#		
lime & shale	2300	BHP 1197# 120 minutes;		
lime (Broken)	2460			
shale & Lime	2865	DST #2 (S) 4294-4298 open 1 hr; fair blow		
shale & shells	2980	1 hr; recovered 90' clean oil,		
shale & Lime	3030	90' muddy oil; 150' water;		
sandy Lime & shale	3060	flow pressures 0- 240#		
shale & Lime	3200	BHP 830# in 20 minutes.		
Lime & shale	3280			
Lime	3435			
Sandy Clay & shale	3490			
Lime & shale	3590			
shale	3677			
Lime & shale	3698			
Lime	3960			
Lime & shale	4055			
Conglomerate	4081			
Mississippian chert	4104			
Kinderhook shale	4110			
shale	4158			
Viola	4190			
Viola chert	4215			
chert & shale	4250			
shale & sand	4271			
Simpson	4293			
Arbuckle	4298			

D &amp; A

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 17 1960  
CONSERVATION DIVISION  
Wichita, Kansas

R. T. D.