

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-125-11008-6006

LEASE NAME Smith

WELL NUMBER 2

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

 Ft. from S Section Line

 Ft. from E Section Line

LEASE OPERATOR D. R. Lauck Oil Co., Inc.

SEC. 16 TWP. 24 RGE. 14W (E) or (W)

ADDRESS 221 S. Broadway, Suite 400 Wichita, KS 67202

COUNTY Stafford

PHONE (316) 263-8267 OPERATORS LICENSE NO. 5427

Date Well Completed

Character of Well Oil

Plugging Commenced 7-30-96

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 8-02-96

The plugging proposal was approved on (date)

by Steve Pfeifer (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4279'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	246'	none
				5 1/2	4277'	732'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set sanded off bottom to 3745' & 5 sks cement. Shot @ 3017', worked pipe. Shot @ 2816', worked pipe. Shot @ 2616', worked pipe. Shot @ 2418', worked pipe. Ran shot to 2220', did not go off. While pulling shot back out of hole it went off at 732' & pipe parted. Pulled out 732' of pipe. Plugged well with 300# hulls, 10 sks gel, 50 sks cement, 10 sks gel, 100# hulls. Release the plug. Mix 125 sks cement down 8 5/8. 60/40 6%-gel. Plugging complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

RECEIVED
KANSAS CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: D. R. Lauck Oil Co., Inc.

STATE OF Kansas COUNTY OF Rice, ss. AUG 15 1996

Mike Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated, and matters herein contained and the log of the above-described well is filed the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) P.O. Box 467 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 14th day of August, 1996

My Commission Expires:

IRENE HERGENROTTER
Notary Public
State of Kansas
My Appt. Exp. Aug. 24, 1997