

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Stafford County, Sec. 15 Twp. 24 Rge. 14 (E) (W)

Location as "NE/CNW/SW" or footage from lines SW SWSW
Lease Owner M.B. Armer
Lease Name Suiter Well No. 1
Office Address 710 Petroleum Building, Wichita 2, Kansas.
Character of Well (completed as Oil, Gas or Dry Hole) dry
Date well completed 6-25 19 53
Application for plugging filed 6-25 19 53
Application for plugging approved 6-25 19 53
Plugging commenced 6-26 19 53
Plugging completed 6-26 19 53
Reason for abandonment of well or producing formation Dry

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production -0- 19 -0-

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well M.A. Rives

Producing formation -0- Depth to top -0- Bottom -0- Total Depth of Well 4,303 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	244'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy Rotary mud, set bottom plug at 230 ft. with 20 sacks cement through drill pipe. Mud to 40 ft top plug with 10 sacks cement at surface

7-3-53

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor

Address

STATE OF Kansas, COUNTY OF Sedgwick, ss.

Merle E. Britting (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature)

Merle E. Britting
710 Petroleum Bldg., Wichita, Kansas.
(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of July, 19 53

My commission expires Feb. 13, 1956

Rose Lusey
Notary Public.



M.B. ARMER

SUITER Well #-1
 SW SW SW Sec. 15-24-14
 Stafford County, Kansas.

Casing Record:
 8 5/8" @ 244' w/ 150 sacks

Elevation: 1,971' D.F.

D. & A.

LOG

Sand	0-110	Shale, Lime & Chert	3933-3969
Shale & Red Bed	110-233	Shale & Lime	3969-4005
Red Bed, Shale & Sand	233-915	Lime	4005-4041
Red Bed, Shale & Shells	915-1340	Chert	4041-4069
Shale & Shells	1340-1680	Lime & Shale	4069-4090
Shale & Lime	1680-1855	Shale	4090-4130
Lime & Shale	1855-2080	Shale & Chert	4130-4162
Lime	2080-2155	Lime	4162-4181
Lime & Shale	2155-2330	Lime & Shale	4181-4205
Shale & Lime	2330-2475	Chert & Shale	4205-4232
Lime & Shale	2475-2570	Lime & Shale	4232-4265
Shale & Shells	2570-2855	Shale	4265-4274
Shale & Lime	2855-2950	Lime	4274-4303
Shale & Shells	2950-3045	T.D.	4303
Shale, Lime & Shells	3045-3155		
Shale & Lime	3155-3255		
Lime & Shale	3255-3330		
Broken Lime	3330-3400		
Lime & Shale	3400-3500		
Broken Lime	3500-3565		
Shale & Shells	3565-3700		
Lime	3700-3895		
Lime & Shale	3895-3933		

Markers
 Corrected Schlumberger
 Tops

Heebner	3,512	-1,538
Brown Lime	3,651	-1,577
Lansing	3,678	-1,604
Mississippi	4,035	-2,061
Viola	4,152	-2,178
Simpson	4,221	-2,247
Arbuckle	4,273	-2,300

M.B. ARMER

By Merle Butting

STATE OF KANSAS }
 } SS
 COUNTY SEDGWICK }

Subscribed and sworn to before me, a notary public, in and for said county and State this 30th day of June, 1953

Lorraine M. Johnson
 Notary Public

My Commission expires October 13, 1956

