

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
5 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-02-3-117

API NUMBER 15-097-20546-00-00

LEASE NAME Emma

WELL NUMBER 1

1980 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 2 TWP. 27S RGE. 16W (E) or (W)

COUNTY Kiowa

Date Well Completed \_\_\_\_\_

Plugging Commenced 11-15-02

Plugging Completed 11-19-02

RECEIVED

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

Dec 2 2002

WICHITA

LEASE OPERATOR BEREN CORPORATION

ADDRESS P.O. Box 20380 Wichita, Kansas 67208

PHONE (316) 265-3311 OPERATORS LICENSE NO. 5364

Character of Well OIL Gas

(Oil, Gas, D&A, SHD, Input, Water Supply Well)

Is the plugging proposal approved on \_\_\_\_\_ (date)

Richard Lacey (KCC District Agent's Name)

ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.O. 4610'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	390'	None
				4-1/2"	4614'	2420'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug material is used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each sack pumped bottom with 55 sacks cement and 100# hulls, shot pipe loose @2420', pulled up to 1050', pumped 10 sacks gel, 50 sacks cement, pulled up to 420', pumped 50 sacks cement, pulled up to 40' and circulated 30 sacks cement to surface, 60/40 pos. 6% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Beren Corporation

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.


(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 27th day of November, 2002

[Signature]  
Notary Public

My Commission Expires:



Form CP  
Revised 05-

OR