

STATE OF KANSAS
STATE CORPORATION COMMISSION
206 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-20624-0000

LEASE NAME Seibert

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER SWDW

SPOT LOCATION 400' FNL and 100' FWL
NW/4

SEC. 15 TWP. 23 SRGE. 15 (EX) (W)

LEASE OPERATOR Robert F. White

COUNTY Stafford

ADDRESS 505 Union Center

Date Well Completed 8-4-76

PHONE # (316) 263-7957 OPERATORS LICENSE NO. 5061

Plugging Commenced 8-7-85

Character of Well SWD
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 8-7-85

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Kansas

Is ACO-1 filed? yes If not, is well log attached? yes

Disposal
Producing formation Cedar Hills Sandstone Depth to top 450' bottom 550' T.D. 590'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	Surface Casing	0	278'	8 5/8	278'	-0- (Cemented)
	Long String	0	565'	4 1/2	565'	-0- (Cemented to bottom)

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. With K.C.C. man present (Leuthe) well casing was cemented top to bottom with cement truck. First water pumped into disposal zone followed by 8 sax of gel and 80 sax of cement - under 150 P.S.I. pump pressure. Filled casing to top - took pressure off and well stood full. Well pipe cut off - cap welded on and buried.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor No plugging contractor (pulling unit) was used. License No.
Address well was plugged by pumping casing full of cement to surface under pressure.
Cement was Allied Cementing Co., Inc. of Russell, Kansas.
Supervision for operation was Lloyd Davis, Russell, Kansas.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Robert F. White ~~Notary Public~~ or
(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Robert F. White

(Address) 505 Union Center

SUBSCRIBED AND SWORN TO before me this 19 day of August, 1985

Carol Pick

Notary Public

Carol Pick

AUG 20 1985

My Commission expires: September 20, 1986

SWDLO - SIEBER

400

450

Packer

1 Joint
Below Packer

482' to 484'

0 perf. with 8 holes

0

0

0

488' to 496'

0 perf. with 32 holes

500

0

0

504' to 510'

0 perf. with 24 holes

550

Robert F. White
Siebert #1 SWD
Sec 5-25S-15W
Stafford Co Kan

O = 5 H.S.L.
TD = 565'
8-4-76

RECEIVED
STATE CORPORATION COMMISSION

JUL 18 1976

CONSERVATION DIVISION
Wichita Kansas