

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-047-21,358-0000

LEASE NAME J. H. Cross

WELL NUMBER #2-17

1815 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 17TWP. 24SRGE. 17 (X) or (W)

COUNTY Edwards

Date Well Completed July 26, 1990

Plugging Commenced 1:00 AM

Plugging Completed 1:30 AM

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR E. G. Holl Company

ADDRESS PO Box 780167 Wichita, Kansas 67278-0167

PHONE# (316) 684-8481 OPERATORS LICENSE NO. 5056

Character of Well dry hole

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on July 25, 1990 (date)

by Dick Capp, Didge City, Kansas (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, Is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	321'KB	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
filled hole with heavy mud. Plugged with 50 sacks at 1180'; 40 sacks at 600';
50 sacks at 350'; 15 sacks 60' to 0'; 15 sacks in rathole. Used 60/40 Pozmix
W/ 6% gel. By Howco.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sterling Drilling Company License No. 5142

Address PO Box 129, Sterling, Kansas 67579

STATE OF Kansas COUNTY OF Rice, ss.

Richard L. Mead

(Employee of Operator) Operator of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Richard L. Mead
Richard L. Mead

(Address) PO Box 129, Sterling, Kansas 67579

SUBSCRIBED AND SWORN TO before me this 27 day of July, 1990

F. A. Wuellner
Notary Public F. A. Wuellner

My Commission Expires: _____



STERLING DRILLING COMPANY

BOX 129

STERLING, KANSAS 67579

WELL LOG -----J.H. Cross 2-17
 165' N SE NE SW, Section 17-T24S-R17W, Edwards County, Kansas

OWNER: F. G. Holl Company

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: July 19, 1990

COMPLETED: July 26, 1990

TOTAL DEPTH: 4560'

LOG

0 - 90'	surface soil and sand
90 - 322'	red bed and shale
322 - 1168'	red bed and shale and lime
1168 - 1179'	anhydride
1179 - 4560'	lime and shale

CASING

Ran 7 joints 8 5/8" 23# new casing.
 308.83' pipe set at 321' KB. Cemented
 with 225 sacks 60/40 Pozmix W/ 2%
 gel, 3% cc. Plug down at 12:00 noon
 by Howco. Good returns to surface.
 7-19-90

Plugged

DEVIATION SURVEYS

1° at 4437'

RECEIVED
 STATE OF KANSAS

JUL 31 1990

CONSERVATION OF LANDS
 Wichita, Kansas