

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117.

15-151-102430000  
API NUMBER 3-23-53  
LEASE NAME SICU  
WELL NUMBER 3-12

7-21-98

RECEIVED  
KANSAS CORP COM

TYPE OR PRINT  
NOTICE: Fill out completely and return  
to Cons. Div. office within 30 days.

1650 Ft. from S 10 Line of Section (circle one)  
330 Ft. from E 10 Line of Section (circle one)

LEASE OPERATOR Iuka Carmi Development  
ADDRESS P.O. Box 847  
CITY, STATE, ZIP Pratt, Ks. 67124-0847  
PHONE#(316) 672-2531 OPERATORS LICENSE NO. 31739  
Character of Well Oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

SPOT LOCATION NW - SW - NW  
SEC. 18 TWP. 27S S. RGE 12 (E) or (W)  
COUNTY Pratt  
Date Well Completed March 1953  
Date Plugging Commenced 6-26-98  
Date Plugging Completed 7-2-98

The plugging proposal was approved on 6-22-98 (date)  
by Steve Pfeifer (KCC District Agent's Name)

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation(s) Upper Simpson & Lower Simpson Depth to Top 4300' Bottom 4323' T.D. 4333'  
Show depth and thickness of all water, oil and gas formations. Upper Simpson 4300' to 4311' P.B.T.D. 4329'  
Lower Simpson 4318' to 4323'

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
	Surface Pipe	0'	442'	8 5/8	442' /	0
	Casing	0	4333'	5 1/2	4333' /	807'

Described in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

6-26-98 Pumped 25sx cement, 200# hulls - Casing tightened at 816' - Shot off at 807'. Pulled 27 joints & one piece of 5 1/2" casing.  
6-29-98 Pumped 20sx gel, 300# hulls, 50sx cement. didn't break circulation  
6-30-98 Pumped 20sx gel, 400# hulls, 25sx hot cement.  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Pratt Well Service Inc  
License No. 5056  
Address P.O. Box 847, Pratt, Ks, 67124-0847

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Richard A. Harris  
STATE OF Kansas COUNTY OF Pratt, ss.

Stephen E. Hart - office manager (Employee of Operator or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Stephen E. Hart  
(Address) c/o P.W.S. Inc.

SUBSCRIBED AND SWORN TO before me this 17th day of July, 1998

Kenneth W. Ferguson  
Notary Public

My Commission Expires: 06/19/00

KENNETT  
Notary Public  
My Appt. Expires 06/19/00

## Plugging Continued

6-30-98 Pumped 80 BBL. drilling mud, 50sx cement w/4% Calcium

7-1-98 Tagged cement at 700' -

Pumped 80 BBLs of Mud, 25 sx, thicker atropic cement at 600'

Pumped 50sx cement w/4% Calcium

7-2-98 Tagged cement at 420'

pumped 50 sx 60/40 & 20 sx

Top of cement 10'8"

Back fill w/ sand

Top off w/ common cement.