


STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 CONSERVATION DIVISION  
 P. O. BOX 17027  
 WICHITA, KANSAS 67137

WELL PLUGGING RECORD

Sedgwick County, Sec. 32 Twp. 29S Rgn. 2W (E) (W)  
 Location as "NE/CNWESW" or footage from lines C SW SE

Lease Owner Arthur J. Gorski - Pan-Western Petroleum, Inc.  
 Lease Name Eagan-Tjaden Unit Well No. 1  
 Office Address c/o Toby Elster, 1313 Union National Bldg., Wichita, KS  
 Character of Well (completed as Oil, Gas or Dry Hole) D & A  
 Date well completed October 18 19 74  
 Application for plugging filed October 18 19 74  
 Application for plugging approved October 18 19 74  
 Plugging commenced October 18 19 74  
 Plugging completed October 18 19 74  
 Reason for abandonment of well or producing formation D & A



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Ted E. Dewey  
 Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4079 Feet  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	258'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Mud to 255'  
 1/2 sk. hulls & plug w/25 sx. cmt.  
 Mud to 40', plug w/10 sx. cmt.

RECEIVED  
 STATE CORPORATION COMMISSION  
 OCT 30 1974  
 CONSERVATION DIVISION  
 Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)  
 Name of Plugging Contractor Red Tiger Drilling Company  
 Address 1720 Wichita Plaza, Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick ss.  
 Linda H. Dickens (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Linda H. Dickens  
 1720 Wichita Plaza, Wichita, Kansas 67202

SUBSCRIBED AND SWORN TO before me this 22nd day of October, 1974

My commission expires December 28, 1977  
 D'Ann Drennan Notary Public.



DRILLERS LOG

No. 1 Eagan-Tjaden Unit

CASING RECORD:

8-5/8" @ 258'  
w/175 sx. cmt.

TOTAL DEPTH: 4079'

COMPANY: Arthur J. Gorski-Pan-Western Pet.

CONTRACTOR: Red Tiger Drilling Co.

COMMENCED: October 5, 1974

COMPLETED: October 18, 1974

DESCRIPTION:

C SW SE  
32-29S-2W  
Sedgwick County,  
Kansas

ELEVATION: 1292' GR

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Clay, Rock, Sand & Shale	0	120	
Sand, Shale & Anhydrite	120	258	
Shale & Shells	258	655	
Shale & Lime	655	2315	
Lime & Shale	2315	3000	Stalnacker Sand 2698-
Lime	3000	3605	2836
Lime & Chert	3605	3735	
Lime	3735	3855	
Lime & Chert	3855	3927	
Lime	3927	4020	
Lime & Sand	4020	4042	
Lime	4042	4049	
Lime & Shale	4049	4079	

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 30 1974  
CONSERVATION DIVISION  
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Linda H. Dickens  
Linda H. Dickens

Subscribed and sworn to before me this 22nd day of October, 1974.

D'Ann Drennan  
Notary Public

My Commission Expires:

December 28, 1977

