

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Sedgwick County. Sec. 15 Twp. 29S Rge. 2 ~~XX~~W  
Location as "NE/CNW 1/4 SW 1/4" or footage from lines \_\_\_\_\_

SW SW SE  
Lease Owner P.V. Properties

Lease Name Stitt Well No. #1

Office Address 360 Sutton Place Wichita, Ks. 67202

Character of Well (Completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Dry Hole.

Date Well completed 6-6 1981

Application for plugging filed 6-6 1981

Application for plugging approved 6-6 1981

Plugging commenced 6-6 1981

Plugging completed 6-6 1981

Reason for abandonment of well or producing formation \_\_\_\_\_


If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Don Thompson

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3597

Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plat

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	440'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Mud to 475', 1/2 sk. hulls, plug, 20 sx. cement.

Mud to 40', 1/2 sk. hulls, plug, 10 sx. cement.

3 sx. in rathole.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor White & Ellis Drilling, Inc.  
401 E. Douglas Suite 500 Wichita, Ks. 67202


STATE OF Kansas COUNTY OF Sedgwick, ss.

Ernest Sifford (employee of owner) or (owner or operator of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ernest Sifford  
401 E. Douglas #500 Wichita, Ks. 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of June, 1981

My commission expires



Carolyn J. Tjaden  
Carolyn J. Tjaden - Notary Public.

RECEIVED  
STATE CORPORATION COMMISSION

JUN 19 1981

CONSERVATION DIVISION  
Wichita, Kansas

**DRILLERS LOG**

OPERATOR: P.V. Properties Inc. 360 Sutton Place Wichita, Ks. 67202

CONTRACTOR: White & Ellis Drilling, Inc., Box 448, El Dorado, Kansas 67042

Lease Name Stitt Well No. #1

Sec. 15 T. 29 R. 2W Spot SW SW SE

County Sedgwick State Kansas Elevation \_\_\_\_\_

Casing Record:

Surface: 8 5/8 @ 440' with 300 Sxs. 3%cc  
2%gel

Production: \_\_\_\_\_ @ \_\_\_\_\_ with \_\_\_\_\_ Sxs.

Type Well: D & A Total Depth 3597'

Drilling Commenced: 5-28-81 Drilling Completed 6-6-81

Formation	From	To	Tops
Cellar	0	7	Kansas City 2930
Shale, Lime	7	672	
Shale	672	1028	
Shale, Lime	1028	1300	
Lime, Shale	1300	1659	
Shale	1659	1908	
Shale, Lime	1908	2133	
Lime, Shale	2133	2336	
Shale, Lime	2336	2589	
Lime, Shale	2589	2712	
Sand	2712	2748	
Lime, Shale	2748	2781	
Shale, Lime	2781	2930	
Lime	2930	3096	
Lime, Shale	3096	3205	
Shale, Lime	3205	3386	
Lime, Shale	3386	3597	

**COMPLETION RECORD**

Liner Record: Size \_\_\_\_\_ From \_\_\_\_\_ To \_\_\_\_\_

Cementing Record: \_\_\_\_\_ Sacks \_\_\_\_\_

Perforating Record:

Formation	Perforated Interval	Number Shots
_____	_____	_____
_____	_____	_____
_____	_____	_____
_____	_____	_____

Initial Production: \_\_\_\_\_

Electric Log \_\_\_\_\_

**RECEIVED**  
STATE CORPORATION COMMISSION Type and Depths Covered

JUN 10 1981

CONSERVATION DIVISION  
Wichita, Kansas