


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:

Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Sedgwick County, Sec. 15 Twp. 29S Rge. 2W (E) (W)
Location as "NE/CNW/KSW" or footage from lines NW NE
Lease Owner Braden Deem, Inc.
Lease Name Chambers #1 Well No.
Office Address Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 3/1/73 19
Plugging completed 3/14/73 19
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Dewey
Producing formation Depth to top Bottom Total Depth of Well 3568 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	457	none
				1 1/2"	3560	213

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set 4 sacks of cement on bottom, rigged up on 4 1/2" casing, shot pipe at 3000', pipe parted, couldn't get on fish. Decided to plug well. Bailed hole to 210', set rock bridge and ran 25 sacks cement. Mudded to 30' and ran 10 sacks cement.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
MAR 24 1973
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNEEZE VOTH CASING PULLING
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE ss.
WALTER VOTH (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Walter Voth
CHASE, KANSAS (Address)

SUBSCRIBED AND SWORN TO before me this 20th day of March, 1973

My commission expires



MARGARET MELCHER
NOTARY PUBLIC
Rice County, Kansas
My Commission Expires
Feb. 15, 1975

Margaret Melcher
Notary Public.

3560' w/sa str
RTD 3,568' OH cmtg CHAMBERS #1

Oil Property Management, Inc.

Total Depth: 3568' Elevation: 1300 GL, 1305 KB
Contractor: Donelson Drilling Co. Location: SE NW NE, 15-29-2W
Commenced: 11/13/67 Sedgwick County, Kansas
Completed: 11/19/67 Surface Casing Record:
451.89' new 8 5/8" set
@ 456.89 w/200 sx cmt.

<u>Formation:</u>	<u>Depth:</u>
Surface hole	458'
Shale & Lime	1460'
Shale	1739'
Anhydrite	1750'
Shale & Lime	2700'
Sand	2768'
Lime & Shale	2935'
Lime (K.C.)	2939'
Lime	3127'
Shale & Lime	3550'
Lime (Miss.)	3568' TD

RECEIVED
STATE CORPORATION COMMISSION
JAN 24 1973
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify the foregoing statements are true and correct to the best of my knowledge and belief.

DONELSON DRILLING COMPANY

James L. Donelson
James L. Donelson

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Subscribed and sworn to before me, a Notary Public in and for said county and state, this 21st day of November, 1967.

My Commission expires: April 16, 1969.

Carolyn L. Scott
Carolyn L. Scott