

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

10-19-81

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 19 1981  
CONSERVATION DIVISION  
Wichita, Kansas

API Number 15-097-20,823

200 Colorado Derby Bldg.  
Wichita, KS 67202

Operator's Full Name Texas Oil & Gas Corp.

Complete Address 2700 Fidelity Union Tower, Dallas Texas 75201

Lease Name Sneed Well No. B-1

Location 990' FNL-330' FEL Sec. 2 Twp. 27S Rge. 16 W (East) (West)

County Kiowa Total Depth 4650'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor H-30 Drilling Co. Inc.

Address 251 N Water Wichita Kans 67202 License No. \_\_\_\_\_

Operation Completed: Hour: 5:00 P.M. Day: 16 Month: October Year: 1981

Plugging Operations attended by Agent? All  Part  None

The above well was plugged as follows:

There is <sup>8 5/8"</sup> 415' of surface casing cement circulated. There was a streak of anhydrite topped at 770' then another at 1020'. 1st plug after circulating for 10 min at 600' with 40 sbs of cement. 2nd plug pushed rubber plug to 395' and pumped 35 sbs of cement on top of rubber plug. 3rd plug 40' to 0' with 10 sbs of cement on solid bridge. Put 5 sbs of cement in each rat hole & mouse hole. They had a water well 75' deep with 5" casing put 5 sbs cement in it. Plugging accomplished by Dow Drilling Co.

I hereby certify that the above well was plugged as herein stated.

DATE 10-29-81

INV. NO. 8489-W

Signed: Paul Luttie  
Conservation Division Agent