

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

11-22-1966

RECEIVED
STATE CORPORATION COMMISSION
NOV 22 1966

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Amarillo Natural Gas Company

Complete Address: 305 Bank of southwest Bldg. Amarillo, Texas

Lease Name Abell "A" Well No. 1

Location C SE SW Sec. 35 Twp. 32 Rge. 23 (X) (W)

County Clark Total Depth 4750'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: None

Plugging Contractor: Mahoney Drilling Co.

Address: Liberal, Kansas License No.

Operation Completed: Hour 3:00PM Day 18 Month 11 Year 1966

The Above well was plugged as follows:

8 5/8" to 568' circulated w/ cement, 4 1/2" to 4749' cemented.

2" Upset tubing to 4250' Top perforations 4458'

Plug bottom w/ 100 sacks cement Top of cement 2750'

Fluid 2750' to 700' 200 sacks cement 700' to 0'.

No Pipe Pulled. Haliburton Pump Truck.

Earth Shifted & 4 1/2" parted at 210' and 8 5/8" collapsed.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 11/22/66

INV. NO. 4325-W

Signed: Edwards Eves
Well Plugging Supervisor