

SKELLY OIL COMPANY

REPORT OF CHANGE IN WELL RECORD

Give complete description of all cleaning out, deepening, plugging back and fishing jobs, changes in casing, material lost in hole, etc., not recorded in original well record.

LEASE NAME J. E. Hateliff WELL NO. 7

CLEANING OUT RECORD					PLUGGING BACK OR DEEPENING RECORD				
Date commenced.....		<u>January 23, 19 48</u>			Date commenced.....		19		
Date completed.....		<u>January 23, 19 48</u>			Date completed.....		19		
Cleaned out from.....		to <u>T. D. PB 3614</u>			Plugged back or deepened from.....		to..... T.D.....		
Prod. before	<u>1</u> bbls. oil	<u>19</u> bbls. water	<u>0</u> cu. ft. gas		Prod. before	bbls. oil	bbls. water	cu. ft. gas	
Prod. after	<u>2</u> bbls. oil	<u>20</u> bbls. water	<u>0</u> cu. ft. gas		Prod. after	bbls. oil	bbls. water	cu. ft. gas	
Kind of tools used:.....					Kind of tools used:.....				
Tools owned by:.....					Tools owned by:.....				

SHOT RECORD

Date	<u>1/25/48</u>					
Size shot	<u>3000</u> gals.	<u>K2</u> Qts.		Qts.		Qts.
Shot between	<u>3578</u> Ft. and	<u>3983</u> Ft.	Ft. and	Ft.	Ft. and	Ft.
Size of shell						
Put in by (Co.)	<u>Dowell Inc.</u>					
Length anchor						
Distance below casing						
Damage to casing or casing shoulder						

RECEIVED
 JUN 5 1967
 CONSERVATION DIVISION
 Wichita, Kansas

CHANGES IN CASING RECORD

SIZE	Wt.	Thds.	Where Set	PULLED OUT			LEFT IN			KIND	Cond'n	CEMENTING	
				Jts.	Feet	In.	Jts.	Feet	In.			Sacks Used	Method Employed

Liner set at..... Length..... Perforated at.....

Packer set at..... Size and kind.....

REMARKS (Give review of work accomplished and any other comment of interest) On January 23, 1948, pulled rods and acidized with 3000 gallons of Dowell "K" acid as follows:

.....

.....

.....

.....

(Use reverse side for continuation of remarks and for formation record).

Superintendent.

REMARKS (Continued)

ACID TREATMENT NO. 7 - Between 3570' and 3583'

Treatment put in 1/25/48 by Howell Inc., using 5000 gallons of acid and 63 barrels of oil to fill hole and flush.

TIME	OP	IP	REMARKS
4:30 PM			Filled hole with 32 barrels of oil
5:04 PM	Vac.	Vac.	340 gallons of acid in hole, on bottom
5:09 PM	Vac.	100	1000 gallons of acid in hole
5:20 PM	Vac.	75	2000 gallons of acid in hole
5:31 PM	Vac.	75	3000 gallons of acid in hole
5:36 PM	Vac.	75	Flushed hole with 17 barrels of oil and treatment completed.

After acid treatment swabbed out oil used in treating. Ran rods and BOB 8 hours, 16 barrels of oil and 35 barrels of water. The next

RECORD OF FORMATIONS

FORMATION	TOP	BOTTOM	REMARKS
-----------	-----	--------	---------

Indicate Casing Points, Describe Shows of Oil, Gas and Water, etc.

16 days the well pumped as follows:

DATE	HOURS PUMPED	BARRELS OIL	BARRELS WATER	REMARKS
1-25-48	8	12	31	
1-26-48	24	20	15	
1-27-48	24	10	22	
1-28-48	4	2	8	Well pumped off
1-29-48	6	0	60	Well pumped off
1-30-48	6	1	17	Well pumped off
1-31-48	24	2	30	
2-1-48	24	2	30	
2-2-48	24	2	30	
2-3-48	24	2	10	Well pumped off
2-4-48	24	2	10	
2-5-48	12	2	30	
2-6-48	8	2	10	
2-7-48	0	2	10	
2-8-48	10	2	10	
2-9-48	24	2	20	