

State of Kansas



JOHN ANDERSON, Jr. Governor
 WILLIAM L. MITCHELL, Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VEREAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

AUG 16 1965

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. George McKown of Garvey Drilling Company has this date requested permission to plug the following described well:

Mr. McKown guarantees payment of the plugging fee.

Operator's full Name: Petroleum Inc.

Complete Address: 352 N. Broadway, Wichita, Kansas

Lease Name: Neill "D" Well No. # 1

Location: NW SE SW Sec. 14 Twp. 24 Rge. 14 (E) (W) W

County Stafford Total Depth 3619' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. McKown was instructed to plug the well as follows:

215' of 8 5/8" surface pipe, cement circulated with 250 sacks.
Fill hole with drilling mud to 210', 1st cementing plug, bridge
with hulls, and cement with 25 sacks. Fill hole with drilling
mud to 40', 2nd cementing plug, bridge with hulls, and cement
with 10 sacks to base cellar. Bridge and cement rat hole with
2 sacks.

Very truly yours,

Archie Elving