

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202
RECEIVED
WICHITA CORPORATION COMMISSION

MAY 3 1971

CONSERVATION DIVISION
Wichita, KansasVERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Johnson of Gabbert & Jones, Inc. has this date requested permission to plug the following described well:

Mr. Johnson guarantees payment of the plugging fee.

Operator's full Name: Black Petroleum Co. Inc.

Complete Address: 445 O.W. Garvey Bldg. Wichita, Ks

Lease Name: Ulsh Well No. 1

Location: NE/NE/SW Sec. 20 Twp. 24s Rge. 14 (E)(W) W

County: Stafford Total Depth 4250 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Johnson was instructed to plug the well as follows:

275 ft of 8 5/8 surface pipe cemented with 225 sacks. Pump
60 sacks cement to 600 ft. Fill hole to 2600 ft, pump 25
sacks cement. Mud to 40 ft, 1/2 sack hulls, plug, 10 sacks
cement to surface. 2 sacks cement in rat hole.

Pumped by Globe Cementing Co. Great Bend, Ks

Very truly yours,

L. Russell B. Bennett
Conservation Division Agent